

Tel +1-210-635-8100 Fax +1-210-635-8101 www.intertek.com



Issue Date: February 12, 2020 Letter Report No: 104152978SAT-001AL.R1

Project No: G104152978SAT

Daniel White ACS Composite Systems, Inc. 35-7450 Butler Road Sooke, BC Canada V9Z 1N1

Phone: +1 (778) 352-1015 Email: dan@acscompositesystems.com

Intertek Letter Report No. 104152978SAT-001AL - Evaluation of ACS's ACP systems-1 with Subject: STACBOND® FR core ACM wall assembly to CAN/ULC S134-13, Standard Method of Fire Test of Exterior Wall Assemblies.

Mr. White

Intertek has concluded an evaluation for ACS ACP systems-1 with 4MM STACBOND® FR core ACM, Intertek Project No. G104152978SAT, for compliance under the following criteria:

CAN/ULC S134-13, Standard Method of Fire Test of Exterior Wall Assemblies

The FR core ACM wall assembly was tested on February 6, 2020.

The samples were tested to the general requirements of CAN/ULC S134-13 on 6 February 2020. The test specimen was composed of SOPRASEAL STICK vapor barrier installed on 5/8 in. gypsum board. 6 in. Cavity Rock Rockwool was used as non-combustible insulation, compression fit between 6 inch ACS S-clips. The ACM panels were then mounted to the assembly using 16GA steel vertical angle. The ambient temperature and relative humidity at the start of the test were recorded to be 57 °F and 21%, respectively. Rick Huggins and Dustin Elder, representing ACS were present to witness the test. The test was conducted for 60 min. Radiometers located at 3.5m above the window opening of the test specimen did not exceed the heat flux limit during the test and flames did not reach 5 m above the window opening.

Based on the results obtained, the wall assembly tested and described herein did meet the requirements of CAN/ULC S134-13.

A full test report will be issued as G104152978SAT-001.











Issue Date: 12 February 2020 Page **2** of **4**

If you have any questions or comments, please contact our office at 210-635-8100, or the undersigned.

INTERTEK TESTING SERVICES NA INC.

Completed by:	Emmanuel Ogoe	Reviewed by:	Herbert W. Stansberry II
Title:	Project Manager, Fire Resistance	Title:	Program Manager Building & Construction
Signature:	Emmanul Oged	Signature:	Henter W. Stand of
Date:	11 February 2020	Date:	12 February 2020

Attachments: Graphical Data


cc: None









ntertek Inter













Issue Date: 12 February 2020
Page 4 of 4

REVISION #	DATE	PAGES	REVISION	
0	02/12/20	N/A	Original Report Issue	
			Revised identification of product tested	
1	02/18/20	1	E.O. HWS	



